

CITY OF LOS ANGELES

CALIFORNIA



ERIC GARCETTI
MAYOR

BOARD OF
BUILDING AND SAFETY
COMMISSIONERS

VAN AMBATIELOS
PRESIDENT

E. FELICIA BRANNON
VICE PRESIDENT

JOSELYN GEAGA-ROSENTHAL
GEORGE HOVAGUIMIAN
JAVIER NUNEZ

DEPARTMENT OF
BUILDING AND SAFETY
201 NORTH FIGUEROA STREET
LOS ANGELES, CA 90012

FRANK M. BUSH
GENERAL MANAGER
SUPERINTENDENT OF BUILDING

OSAMA YOUNAN, P.E.
EXECUTIVE OFFICER

David J. Dunn
CuraFlo IP LLC
4035 E. Oasis St
Mesa, AZ 85215

RESEARCH REPORT: RR 5689
EFFECTIVE DATE: 7/1/2018
EXPIRATION DATE: 7/1/2019
Telephone: 440-477-5164

GENERAL APPROVAL – Renewal - CuraPoxy® FS Epoxy Barrier Coating for internal Fire Protection Piping, offered by CuraFlo IP LLC.

DETAILS

This research report approves CuraFlo and contractors approved by CuraFlo to use a proprietary process of cleaning and lining inside of fire service water pipes using CuraPoxy® FS epoxy barrier coating. The coating increases the corrosion resistance of metallic pipes. The insides of the pipes are first cleaned with a non-toxic abrasive process to remove corrosive buildup, burrs, solder drips, etc. and prepared for the application of the barrier material. The epoxy barrier coating material is applied in accordance with the manufacturer's specifications with thicknesses ranging from 8 to 120 mils depending on application. Once cured, the pipes are cleaned and ready for use.

The approval is subject to the following conditions:

1. This process is approved for fire protection applications as follows:
 - a. Metallic steel and copper piping systems from 1" to 12" nominal pipe sizes.
 - b. In new and existing systems.
 - c. In all types of constructions.
2. This process is not approved as a method of repairing and concealing cracks, holes leaks, or other imperfections in the piping system.
3. A fire sprinkler permit shall be obtained for each installation of this product prior to beginning construction. The permit fees shall be based on the fees to replace sprinkler

RR-5689
Page 1 of 4

heads for the total number of heads installed in the lined system. The permit fees for a standpipe system shall be based on the total number of risers to flush.

4. Inspection:

- a. It is the responsibility of the installer to demonstrate to the satisfaction of the Fire Sprinkler Inspector that the system will continue to function as designed after the system has been epoxy lined.
- b. The lined piping system shall be pressure tested to the satisfaction of the Fire Sprinkler Inspector. New and existing piping systems using factory or field-lined pipe shall be hydrostatically tested at 200 psi and shall maintain that pressure without loss for 2 hours. Portions of systems normally subjected to system working pressures in excess of 150 psi shall be tested at a pressure of 50 psi in excess of system working pressure without loss for 2 hours.
- c. All valves shall be operated to demonstrate to the inspector that they remain functional.
- d. Additional inspections may be required at the discretion of the inspector.

5. Field installations shall be performed as follows:

- a. Only CuraFlo and contractors approved and authorized by CuraFlo are allowed to use the process approved under this research report.
- b. Existing systems to be lined shall be in good conditions, free from cracks, holes, leaks or other imperfections in the piping systems. Piping materials with leaks or visual signs of corrosion or damage shall be replaced prior to being lining.
- c. The pipe cleaning and coating process shall be conducted in accordance with ANSI/AWWA Standard No. C210-97 and the manufacturer's printed instructions. When in conflict, the latest edition of the manufacturer's printed instructions approved by the Mechanical Testing Laboratory shall prevail.
- d. The lining shall only be used in rigid piping systems. It shall not be applied across fittings or joints designed to allow mechanical flexibility in the system.
- e. Pipes shall be fully cleaned and prepared prior to applying any coatings. The cleaning of pipes and piping systems and the lining process shall be performed in accordance with the printed instructions of the manufacturer. After coating, pipes shall be allowed to fully cure, and then be flushed for a minimum of 1 hour.
- f. Valves and sprinklers and other components which could be damaged or rendered nonfunctional by the cleaning or epoxy lining process shall be removed prior to

cleaning and coating and reinstalled after flushing. Only new sprinklers of the same type (i.e. discharge type, orifice size, temperature rating, etc.) shall be reinstalled in the lined system.

6. Repairs to lined piping systems shall be performed as follows:
 - a. Repairs shall be done in accordance with the manufacturer's written instructions.
 - b. Only CuraFlo and contractors approved and authorized by CuraFlo are allowed to perform field lining of pipes.
 - c. All replacement components, including pipes and fittings installed in a lined piping system, shall be factory lined or field lined by CuraFlo or contractors approved and authorized by CuraFlo. Unlined components shall not be used.
 - d. Replacement joints shall be joined with threaded, compression or by other approved mechanical means. Joints shall not be made with techniques utilizing heat. If heat is used in the disassembly of lined systems, any heat affected epoxy shall be removed and the pipe shall be recoated. Compression type joints shall be joined prior to lining the pipe.

7. Coated pipes shall be labeled. The labels shall indicate the name "CuraPoxy® FS Epoxy Barrier Coating," and include a disclaimer not to replace pipes without contacting CuraFlo. The labels shall be either tags or decals which shall be attached to the outside of the pipe at the following locations:
 - a. At all valve change outs.
 - b. At water service shutoff valves.
 - c. At standpipe outlets.
 - d. In systems along pipes at intervals not to exceed 20 feet except for existing piping located in concealed and inaccessible areas.
 - e. At piping access points.

CuraFlo IP LLC
Re: CuraFlo® FS Epoxy Barrier Coating

DISCUSSION

Mechanical Testing Laboratory reviewed recent listing certificates. This product has been tested and is currently listed by ICC Evaluation Services, LLC in accordance with Standard ASTM F2831. The materials and construction are equivalent to that prescribed by the Los Angeles Municipal Code in quality, strength, effectiveness, durability and safety.

For this General Approval to be valid on any individual construction project in the City of Los Angeles, an engineer or inspector of the Department of Building and Safety must make a determination that all conditions of the General Approval required to provide equivalency have been met in the case of each construction project under consideration.

The approval is granted under Sections 94.301.0 and 94.2010.0 of the Los Angeles Plumbing Code (LAPC), 2017 Edition.

Approved by:



Irene Pool
Mechanical Testing Laboratory
Permit and Engineering Bureau